

Estimate Works Painting Inc.
P.O. Box 522
Seattle, WA 12345
Phone: (123) 456-7890 Fax: (123) 456-7890

Work Order

Estimator: Suzanne Prior
Job No: 141
Estimate Date: Apr-5-2007

Client:
Gene XSample2
Home Phone: 817-998-8765
Work Phone: 817-485-9998
Cell:

Site Address:
138 Birch Brook Road
Port Angeles, WA 10708

Site Phone: 817-998-8765

Crew:

Site Description: Exterior Preparation and Painting/Staining

Actual Start Date:

Comment:

Actual End Date:

Front Total Area: 1,020 sq. ft. Length: 0.0 ft.
sq. ft. Width: 51.0 ft.
Height: 20.0 ft.

Item Type	Item Description	Quantity	Coats	Gallons	Hours	Actual Hours	Date	Color/Comment
WALL	Power Washing to Remove Dirt & Mildew	1,020 sq.ft.	1		2.3			
WALL	Shingle/Shake (Smooth) - Oil Stain	1,020 sq.ft.	1	3.7	11.3			
SOFFIT	Flat Soffit - Standard Preparation	90 lin.ft.	1		3.0			
SOFFIT	Flat Soffit (2nd Floor) - Prime Coat	90 lin.ft.	1	0.6	4.5			
SOFFIT	Flat Soffit (2nd Floor) - Latex Paint	90 lin.ft.	1	0.6	4.5			
TRIM	Fascia - Standard Preparation	60 lin.ft.	1		2.5			
TRIM	Fascia (2-4") - Prime Coat	60 lin.ft.	1	0.1	1.2			
TRIM	Fascia (2-4") - Latex Paint	60 lin.ft.	1	0.1	1.2			
TRIM	Caulking (Windows, Doors & Trim)	60 lin.ft.	1	0.6	1.0			
DOOR	Door & Frame - Standard Preparation	3 ea.	1		1.5			
DOOR	Door & Frame (1-3 Panel) - Latex Paint	3 ea.	2	0.3	4.5			
DOOR	Door Frame (Standard) - Latex Paint	2 ea.	2	0.1	1.0			
WINDOW	Window & Frame - Standard Preparation	12 ea.	1		4.0			
WINDOW	Window Frame (Standard) - Prime Coat	12 ea.	1	0.3	4.0			
WINDOW	Window Frame (Standard) - Latex Paint	12 ea.	1	0.3	4.0			
WINDOW	Shutter Standard Preparation (Pair)	9 ea.	1		3.0			

Front

Total Area: 1,020 sq. ft. Length: 0.0 ft.
 sq. ft. Width: 51.0 ft.
 Height: 20.0 ft.

Item Type	Item Description	Quantity	Coats	Gallons	Hours	Actual Hours	Date	Color/Comment
WINDOW	Shutter (Standard) - Latex Paint	18 ea.	2	0.6	12.0			
WINDOW	Dormer Standard Preparation	2 ea.	1		1.5			
WINDOW	Dormer - Prime Coat	2 ea.	1	0.3	2.8			
WINDOW	Dormer - Latex Paint	2 ea.	1	0.3	2.8			
EXTRA	Special Staging/Ladder Conditions	1 ea.	1		1.0			

Subtotal: **7.9** **73.6**

Total Actual Hours:

Setup/Cleanup Hours: **4.2**

Job Item Hours: **73.6**

Total Job Hours: **77.8**

Total Actual Hours:

Total Materials (gallons): **7.9**

Job No: 141